



Acel part number AC0599

Solar Commissioning Multifunction Tester

Insulation Test

Tests a Single Module, String or an Entire Photovoltaic Field up to 1000V

Open Circuit Voltage Measurement

Short Circuit Current Measurement

Continuity Measurement

Polarity

Auto Sequence

Technical Specification

Attribute	Value
Insulation Measurement	Up to 1000V DC
Open Circuit Voltage	Up to 1000V DC
Short Circuit Current	Up to 15Amp at 1000V DC
Continuity	200mA
Polarity	Yes
Auto Sequence	Yes
Performance Logging	Yes
Optional Reference Unit	Yes (HT304N)
Hard Carry Case	Yes

9-AC0599-2023-V1